

## TECHNICAL SPECIFICATIONS

### 1. SCOPE OF WORK

The scope of work under this contract shall include tree removal, tree trimming, stump removal/grinding, cleaning of site including removal of all debris, tree leaves, tree branches, tree clippings, etc. and restoration of the site to its original condition. When stump grinding is required, stumps shall be removed 6" to 1' below grade, grindings may be placed in hole; excess shall be removed. Disposal of all debris and waste associated removal/trimming of trees shall be the responsibility of the contractor to dispose of in compliance with all Federal, State and Local Laws. The Contractor shall furnish all labor, materials, and equipment required to perform the work specified under this contract.

The Contractor shall be or employ an ISA Certified Arborist and provide proof of certification.

The Contractor shall be able to provide the services required under this contract during the holidays and weekends, if required.

Should the Contractor not comply with the requirements as set forth in these contract documents, the Owner reserves the right to seek the required services from another Contractor.